

EXTERNAL WORKS LEGEND

Retire boundary

Paving

PT01(A) - Plaza Level Paving - Premium granite water-etched paving blocks - 250mm x 250mm with running course to edge of paving

PT01(B) - Plaza Level Paving - Premium granite water-etched paving blocks - Laid in (dry) colour - 150mm wide x 120mm thick. Random lengths (500 - 250mm) with running course to edge of paving

PT02 (Hazard paving) - Granite kerbside slabs - FLAME TEXTURED contrasting colour - Diamond seen

PT03 - Green Sphal - FLAME TEXTURED Green colour - Diamond seen - 300 x 150mm

PT04 - Granite unit - FLAME TEXTURED light grey - Diamond seen - 300 x 150mm

PT05 - Asphalt

PT06 - Bound Gwail

PT07 - Corian pebbles and rocks of varying sizes up to large boulders, to be placed on a minimum 100mm depth of stone under sand layer

Edges

ED01 - Granite kerbs - Insulated finish Dark grey colour - 300mm(x) x 255mm(x) & 100mm(x) x 255(x)

ED02 - Concrete kerbs - Insulated finish Dark grey colour - 150mm(x) x 255mm(x)

Walling

WAL01 - Concrete wall with cast natural stone blocks inside and outside face with stone coping

Street furniture

SFB01 - Railings - See drawing no. FBS-AHR-S1-XX-DR-L-90102 for railing detail

SFB04 - Granite curb form embellishes and water feature seating edges - Contrasting colour to meet Building Regulations for precast concrete only where they form a finished boundary

SFB05 - Flower bedset

SFB06 - Flower bedset

SFB07 - Litter bins

SFB08 - Curb heap - various see design code for selection

Soft landscape

SO01 - Ornamental & native shrub planting - topsoil depth 450mm & 75mm ornamental bank width


SO02 - Wildflower Grass Mix - topsoil depth 150mm

SO03 - Ornamental hedge, double staggered row - tree plants 0.2m - hedge protection post & three wire fence between rows

SO04 - Ornamental & native tree planting in soft landscape. Specification a combination of semi-mature & (S1) extra heavy standard specimens

Level M0 - Southern Boulevard Plan - Landscape Masterplan
1 : 200

1



Rev	Description	Date	By	App'd	
P010	(D1) For Tender	23/11/18	DH	AJS	
P009	(D1) For Contract	23/10/17	CH	DJK	
P008	(D1) Updated to suit clarification requests	23/02/18	AJB	DJK	
P007	(D1) View extent amended	22/11/15	AJB	AJS	
P006	(D1) Updated issue for RIBA Stage 4	22/11/14	AJB	AJS	
P005	(D1) Issue for RIBA Stage 4	22/02/11	AJB	AJS	
P004	(D1) Revised For Costing	20/06/03	AJB	SO	
P003	(D1) Issued For Costing	20/04/02	AJB	AJS	
P002	(S0) Layout & Red Line Updated	20/04/11	AJS	AJS	
P001	(S2) Issued for Stage 2 costing	20/02/22	DJK	AJS	
Rev	Description	Date	By	App'd	
approved by	DJK	date made	02/21/22	approved by	AJS



client name	Somerset West and Taunton
project	Firepool Masterplan
drawing	External Works - General Arrangement
computer file	20210444_000_P010.dwg
project number	2021.00444.000
drawing number	FBS-AHR-S1-XX-DR-L-90100
scale	1 : 200
sheet	@A0
no	P010
issue status	D1

This drawing is to be used in conjunction with all related drawings. All dimensions must be checked and verified on site before commencing any work or producing shop drawings. The copyright should be retained immediately if any work or shop drawings are produced. This copyright is retained immediately if any work or shop drawings are produced. This drawing is copyright and remains the property of AHR.